

## TNT-el



- » Fully meets AS/NZS 3760
- » Simple One Button Testing
- » Tests Extension Leads
- » Robust Construction
- » Mains Supply Test
- » Earth Bond Test
- » Insulation Test
- » Earth Leakage Test
- » PC Connectivity Option
- » Memory Option

If you need to Test 'n' Tag, there is no other unit that comes close in price or quality as well as adhering to the specifications outlined by the AS/NZS 3760 standard.

The TNT-el Portable Appliance Tester is a low cost, Australian made, advanced safety tester that is ideal for all general testing requirements. This unit tests sensitive electronic equipment that cannot be tested using a standard insulation tester. The TNT-el is simple to use with one button testing, and has a PASS/FAIL indicator. The unit also displays the actual test readings.

**\$850.00** + GST

[www.tagsdirect.com.au](http://www.tagsdirect.com.au)

The TNT-el is a simple to use hand held Portable Appliance Tester designed to test the electrical safety of earthed & double insulated 240V AC rated appliances.

The TNT-el also equipped to test IEC extension leads without requiring a separate adaptor to check for polarity.

Designed & Manufactured in Australia, the TNT-el complies with the requirements of the AS/NZS 3760 Standard.

Simple one button automatic testing makes this unit fast & easy to use. A large clear backlit LCD display shows digital readings of test results & provides prompts to the operator throughout the sequence.

The TNT-el simplifies testing & saves time.

### What you get

- »» TNT-el
- »» Instruction Book
- »» IEC Socket to 3-pin Plug Lead
- »» Earth Bond Lead
- »» Soft Carry Case

### Other Accessories Available

WinPATS™ MX Software  
Tag Printer  
Scanner  
3 Phase Adaptor  
Tinned Copper Braid  
Test n Print Pack



## TESTS PERFORMED

### CLASS 1 Earthed Appliance

- »» **Appliance Check:** Ensures appliance is plugged in and turned on.
- »» **Earth Bond Test:** 200mA Test Current, Pass Level less than 1
- »» **Insulation Test:** 500VDC / 250VDC Test. Pass level greater than 1 M .
- »» **Earth Leakage Test:** 240VAC Mains. Pass level 5.0mA

### CLASS II Double Insulated Appliance

- »» **Appliance Check:** Ensures appliance is plugged in and turned on.
- »» **Insulation Test:** 500VDC / 250VDC. Pass level greater than 1 MO. Measures up to 10 M .
- »» **Earth Leakage Test:** 240VAC Mains. Pass level 1mA

### Extension Leads

- »» **Earth Bond Test:** 200mA Test Current, Pass level less than 1 .
- »» **Continuity / Polarity Test:** 250VAC check continuity & polarity of leads.
- »» **Insulation Test:** 500VDC / 250VDC. Pass level greater than 1 M .

### Mains Supply Test

- »» Checks Polarity & Continuity of mains supply by LEDs A-N, N-E, A-E

### RCD Testing

- »» Leakage Test only 2.5 mA